

PROPOSED HALL AT
VILLAGE KAIMRI

TITLE:-FOUNDATION DETAIL

DRG NO.

JOB NO:EB/23/6/HR

GENERAL NOTES:-

1. BEARING CAPACITY OF SOIL HAS BEEN ASSUMED 08.00 T/M²
2. GRADE OF CONCRETE M-20(1:1½:3)
3. GRADE OF STEEL Fe-500
4. NOMINAL COVER FOR FOOTINGS 60 MM
5. NOMINAL COVER FOR COLUMNS 50 MM
6. NOMINAL COVER FOR BEAMS 25 MM
7. NOMINAL COVER FOR SLAB 25 MM
8. LENGTH OF EXTRA BAR TO BE L/3.
9. STRUCTURE DESIGN IS FOR G.F.F&S.F ONLY
10. LAP LENGTH OF STEEL REINFORCING BARS SHALL BE



11. STANDARD 'L' HOOKS SHALL BE PROVIDED AT THE ENDS OF ALL BARS
12. COL. TIES 8Ø/4"C/C IN END REGION (L/4) & 6"C/C IN MID REGION

TERRAS GEO STRUCTURES

Er. A.R.Saini
Executive Engineer- Structures, CCSHAU
Head Engineering , MHU Karnal
Chartered Engineer, IEI INDIA
CE NO:- F-1190152 DATED:17-07-2018
Fellow Inst. of Valuers, India
IOV NO:- F-28724 DATED:25-06-2019

Er. Sandeep Saini
M.Tech Civil(Geo-Tech)
Chartered Engineer
Structural Consultant on Panel (HSVP)

ENGINEERS, BUILDERS,
STRUCTURAL
CONSULTANTS

Institution of Engineers
Regd. No. -AM 162111-7



DATE:-
09/02/2024

ENGINEER: SANDEEP SAINI

MODELLING: PARVEEN SAINI

CHECKED BY: A.R.SAINI

SCALE:-NTS

