




LAYOUT PLAN OF MAIN BUILDING/
COLUMN & FOUNDATION LAYOUT PLAN

SCHEDULE FOR DETAIL OF COLUMN FOOTING

COLUMN FOOTING			DIMENSION			REINFORCEMENT FOR FOOTING		PEDESTAL DIMENSION	
	L	B	H1	H2	D	R	S	L1	B1
F1	6'-6"	6'-0"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-3"	2'-0"
F2	7'-0"	6'-3"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-3"	2'-0"
F3	8'-6"	8'-0"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-3"	2'-0"
F4	8'-6"	6'-6"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-3"	2'-0"
F5	5'-6"	5'-0"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-3"	2'-3"
F6	5'-6"	5'-0"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-0"	2'-0"
F7	8'-6"	7'-0"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-3"	2'-0"
F8	7'-6"	5'-6"	9"	2'-0"	3'-6"	10Ø TOR 6" C/C	10Ø TOR 6" C/C	2'-3"	2'-0"

- NOTES:-
- * NET BEARING CAPACITY OF SOIL IS 8.0 T/m².
 - * STRUCTURE IS DESIGNED AS SINGLE STOREYED BUILDING FOR SEISMIC ZONE -IV.
 - * IF THERE IS ANY DISCREPANCY REGARDING DIMENSIONS, ARCHITECTURAL DRAWINGS MAY BE CONSULTED.
 - * WRITTEN DIMENSIONS SHOULD BE FOLLOWED.
 - * DRAWING IS NOT TO BE SCALED.
 - * Ø TOR MEANS DIAMETER IN MM FOR TOR STEEL BARS.
 - * STEEL SHUTTERING IS TO BE USED FOR ALL CONCRETE WORKS.
 - * STEEL OF COLUMN TO GO UP TO BOTTOM OF FOUNDATION WITH BEND OF 1'-0" AT BOTTOM .
 - * LEAN CONCRETE WILL BE 6" TH. IN MIX 1:4:8.
 - * LEAN CONCRETE WILL PROJECT 3" BEYOND THE R.C.C FOUNDATION.
 - * COVER TO REINFORCEMENT OF COLUMNS WILL BE 40MM ON ALL FACES.
 - * COVER TO REINFORCEMENT OF FOUNDATION SLAB WILL BE 3".
 - * DEVELOPMENT LENGTH(L_d) OF STEEL IS 57 TIMES THE DIAMETER OF THE BAR.
 - * CEMENT MORTAR RATIO IN 9"TH. BRICK WORK IS 1:6.
 - * CEMENT MORTAR RATIO IN 4½"TH. BRICK WORK IS 1:4.
 - * WHEREVER THE GAP BETWEEN TWO FOOTINGS IS LESS THAN 3'-0", THE LEAN CONCRETE(P.C.C) SHALL BE LAID CONTINUOUSLY.
 - * EARTH FILLING IN FOUNDATIONS SHOULD BE DONE EQUALLY ON BOTH SIDES OF FOUNDATION WALL.
 - * M-20 (1:1½:3) GRADE CONCRETE TO BE USED IN ALL CONCRETE WORKS.
 - * STEEL REINFORCEMENT IS Fe 500 D
 - * NOT MORE THAN 50% BARS SHALL BE SPLICED AT ONE SECTION.

ENGINEER :-

CLIENT :-
XEN PANCHAYATI RAJ,NUH

PROJECT :-
STRUCTURAL DRAWINGS OF PANCHYAT GHAR AT VILLAGE GHASERA,DISTT.NUH

TITLE :-
PANCHYAT GHAR

SUB TITLE :-
LAYOUT PLAN OF MAIN BUILDING AND COLUMN & FOUNDATION LAYOUT PLAN

DRG. NO. :-
JC/PR/NUH/2420/1

SCALE :-
1 : 100

DATE :-
9 July 2022

DRAWN BY :-
SIMRAN

DSN BY :-
JASBIR

CKD. BY :-
K.B. MANOCHA

JC TECHNOCRATS PVT. LTD.
(Formerly known as Jindals Consortium, Since 1990)
STRUCTURAL ENGINEERS, HIGHWAY & BRIDGE DESIGNERS, PROJECT MANAGEMENT CONSULTANTS
ROAD SAFETY AUDITORS, PROOF CONSULTANTS, SURVEYORS AND SOIL INVESTIGATORS
REGD.OFF.: S.C.F.-9, VIKAS VIHAR, AMBALA CITY-134003, HARYANA. PHE: 0171-2550913, MOB:-91-98966-70914
DELHI : # 678, GREEN VIEW APARTMENTS, SECTOR 19, POCKET-2, DWARKA, NEW DELHI. MOB:-91-99964-70914
Mob:- 8199907006, 9896559913, e-mail: jindalstructure@gmail.com, jindals13@gmail.com, Web: www.jindalconsortium.in