





BAR NO. :- 1 TO 6 - 16ØTOR MAIN STEEL
RING 8ØTOR 2 LEGGED @4"C/C THROUGHOUT
ROOF BEAM -B4


BAR NO :- 1 TO 8 - 16Ø TOR MAIN STEEL
RINGS :- 8Ø TOR 2 LEGGED@6" C/C THROUGHOUT
ROOF BEAM -B5

BAR NO :- 1 TO 6 - 16Ø TOR MAIN STEEL
RINGS :- 8Ø TOR 2 LEGGED@6" C/C THROUGHOUT
ROOF BEAM -B6

ROOF BEAMS LAYOUT PLAN




ROOF BEAM -B1




BAR NO. :- 1 TO 8 - 20ØTOR MAIN STEEL
BAR NO. :- 9,10 - 20ØTOR EXTRA BAR ON TOP FACE ON SUPPORTS
RING 8ØTOR 2 LEGGED @4"C/C THROUGHOUT

ROOF BEAM -B1




ROOF BEAM -B2




BAR NO. :- 1 TO 3 - 20ØTOR MAIN STEEL
BAR NO. :- 4 TO 6 - 16ØTOR MAIN STEEL
BAR NO. :- 7,8 - 20ØTOR EXTRA BAR ON TOP FACE ON SUPPORTS
RING 8ØTOR 2 LEGGED @4"C/C THROUGHOUT

ROOF BEAM -B2



ROOF BEAM -B3



BAR NO. :- 1 TO 6 - 16ØTOR MAIN STEEL
BAR NO. :- 7,8 - 16ØTOR EXTRA BAR ON TOP FACE ON SUPPORTS
RING 8ØTOR 2 LEGGED @4"C/C THROUGHOUT

ROOF BEAM -B3

- NOTES:-
- * IF THERE IS ANY DISCREPANCY REGARDING DIMENSIONS, ARCHITECTURAL DRAWINGS MAY BE CONSULTED.
 - * WRITTEN DIMENSIONS SHOULD BE FOLLOWED
 - * MIXER & VIBRATOR ARE TO BE USED FOR ALL CONCRETE WORKS
 - * M-20 (1:1½:3) GRADE CONCRETE TO BE USED IN ALL CONCRETE WORKS.
 - * R.C.C SLAB THICKNESS IS 5".
 - * STEEL REINFORCEMENT Fe- 500 D IS USED .
 - * COVER TO REINFORCEMENT IN BEAM WILL BE 25MM ON BOTH SIDES
 - * COVER TO REINFORCEMENT OF SLAB WILL BE 20MM AT BOTTOM & 12MM AT TOP
 - * CHAIRS OF 10MM TOR STEEL IS TO BE PROVIDED TO SUPPORT CRANKED/ EXTRA STEEL BARS
 - * IN CANTILEVER SLAB & BEAM, COUNTER WEIGHT STEEL WILL BE 1½ TIMES THE LENGTH OF CANTILEVER
 - * LENGTH OF EXTRA BAR AT CONTINUOUS SUPPORT OF BEAM WILL BE L/3 ON BOTH SIDES FROM CENTER OF SUPPORT, WHERE L IS SPAN FROM C/C
 - * LENGTH OF EXTRA BAR AT CONTINUOUS SUPPORT OF SLAB WILL BE L/4 ON BOTH SIDES FROM CENTER OF SUPPORT, WHERE L IS SPAN FROM C/C
 - * OVER LAP LENGTH OF STEEL IS 57 TIMES THE DIAMETER OF THE BAR.
 - * AT SUPPORT, CRANK WILL START AT L/5 FROM CENTER OF SUPPORT, WHERE L IS SPAN FROM C/C
 - * MINIMUM SPACING BETWEEN TWO LAYERS OF REINFORCEMENT IN BEAMS WILL BE 25MM
 - * WHEN TWO BEAMS HAVE DIFFERENT STEEL AT ONE SUPPORT, MAXIMUM OF THE TWO IS TO BE PROVIDED UPTO L/3 OF NEXT SPAN.

ENGINEER :-			
CLIENT :- XEN PANCHAYATI RAJ, NUH			
PROJECT :-			
STRUCTURAL DRAWINGS OF PANCHYAT GHAR AT VILLAGE GHASERA, DISTT. NUH			
TITLE :-			
PANCHYAT GHAR			
SUB TITLE :-		DRG. NO. :-	
ROOF BEAM LAYOUT PLAN & DETAIL		JC/PR/NUH/2420/4	
SCALE :-	DATE :-	DRAWN BY:-	DSN BY:- CKD. BY:-
1 : 100	9 July 2022	SIMRAN	JASBIR K.B. MANOCHA
 JC TECHNOCRATS PVT. LTD. (Formerly known as Jindals Consortium, Since 1990) STRUCTURAL ENGINEERS, HIGHWAY & BRIDGE ENGINEERS, PROJECT MANAGEMENT CONSULTANTS ROAD SAFETY AUDITORS, PROOF CONSULTANTS, SURVEYORS AND SOIL INVESTIGATORS OFFICE: 409, GREEN VIEW APARTMENTS, SECTOR 10, POKHARA, JALPAIGURI, WEST BENGAL, INDIA. PIN-731103. MOBILE: 9830099000 MAIL: jindaltechnocrats@gmail.com, jindal17@gmail.com, Web: www.jindaltechnocrats.com			