Detailed Estimate

Development and Panchayat,Haryana

Office Name:

Division : Executive Engineer, Panchayati Raj[Executive Engineer Rohtak]

Circle :SE PANCHAYATI RAJ CIRCLE ROHTAK [Superintendent Engineer Rohtak]

Name of Work -{**Code}**: Construction of Dalhayan wali choupal on panchyat land at village Ishmaila-9b (Bhupender Singh Hooda VAGY 2023-24) **[DEV/2023-24/114017]**

Estimate Cost: Rs. 11.53 Lakhs [Adm. Approved Status : Yes, 15/03/2024]

Technical Approval Cost: Rs. 11.56 Lakhs

Revised Adm Approval Cost: Rs. 0.00 Lakhs

Item Type	Item Cost	Total Charges	Total Cost
HSR Items	₹9,29,055	₹2,22,973	₹11,52,028
NS Items	₹4,260	₹43	₹4,303
Total	**₹9,33,315**	**₹2,23,016**	**₹11,56,331**

Days in which work is likely to be completed: 220 Days

Location of Estimate Village:ISMALIA 9 BISWA

Assembly Constituency: GARHI SAMPLA - KALOI

District: ROHTAK

Work Category: Other

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Detailed Estimate

Development and Panchayat,Haryana

Work Name: Construction of Dalhayan wali choupal on panchyat land at village Ishmaila-9b (Bhupender Singh Hooda VAGY 2023-24)

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
	Main-Component : Const of Delhyan wali choupal						
	Sub-Component :- Const of choupal Civil Work						
1	HSR	HSR Item ***9.11.1-***10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobri leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat: 1. With common burnt clay non-modular brick tile of class designation 10 **HSR Rate(Rs.) 488.00 Through Rate**	Sqm	98.768	488.00	48199	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		ROOF	*1.00*	*10.287*	*9.601*	*0.000*	*98.768*
							98.768
2	HSR	HSR Item ***11.5.3-***12 mm cement plaster of mix : 3. 1:4 (1 cement: 4 fine sand) **HSR Rate(Rs.) 84.00 Through Rate**	Sqm	69.492	84.00	5837	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		OUTER	*1.00*	*10.058*	*5.182*	*0.000*	*52.119*
		OUTER	*1.00*	*3.353*	*5.182*	*0.000*	*17.373*
							69.492
3	HSR	HSR Item ***11.65.1-***Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer`s specification. 1. Two or more coats on new work **HSR Rate(Rs.) 31.00 Through Rate**	Sqm	242.489	31.00	7517	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		INNER	*2.00*	*10.287*	*3.962*	*0.000*	*81.522*
		INNER	*2.00*	*9.601*	*3.962*	*0.000*	*76.088*
		SLAB	*1.00*	*10.287*	*9.601*	*0.000*	*98.768*
		D	*2.00*	*1.067*	*2.591*	*0.000*	*-5.528*
		W	*3.00*	*1.829*	*1.219*	*0.000*	*-6.689*
		V	*3.00*	*1.219*	*0.457*	*0.000*	*-1.672*
							242.489

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS

Sr. No.	Type	Category/Description / Item Size	Unit	Quantity	Unit Rate (Rs.)	Total Amount (Rs.)	
4	HSR	HSR Item ***11.60-***Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. **HSR Rate(Rs.) 59.00 Through Rate**	Sqm	221.460	59.00	13066	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		SAME AS TOTAL PLASTER	*1.00*	*1.000*	*221.460*	*0.000*	*221.460*
							221.460
5	HSR	HSR Item ***11.93.1-***Finishing walls with water proofing cement paint of required shade : 1. New work (Two or more coats applied @ 3.84 kg/10 sqm) **HSR Rate(Rs.) 39.00 Through Rate**	Sqm	67.448	39.00	2630	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		OUTER	*1.00*	*10.058*	*5.029*	*0.000*	*50.586*
		OUTER	*1.00*	*3.353*	*5.029*	*0.000*	*16.862*
							67.448
6	HSR	HSR Item ***9.17.1-***Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : 1. In 75x75 mm deep chase **HSR Rate(Rs.) 112.00 Through Rate**	Metre	39.776	112.00	4455	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		ROOF	*2.00*	*10.287*	*0.000*	*0.000*	*20.574*
		ROOF	*2.00*	*9.601*	*0.000*	*0.000*	*19.202*
							39.776
7	HSR	HSR Item ***9.59.2-***Providing and fixing Unplasticised -PVC pipe clips of approved design to Unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete. 2. 110 mm **HSR Rate(Rs.) 147.00 Through Rate**	Each	6.000	147.00	882	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		CLIP	*1.00/6.000*	*0.000*	*0.000*	*0.000*	*6.000*
							6.000
8	HSR	HSR Item ***9.18-***Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete. **HSR Rate(Rs.) 147.00 Through Rate**	Each	2.000	147.00	294	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		ROOF	*1.00/2.000*	*0.000*	*0.000*	*0.000*	*2.000*
							2.000

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
9	HSR	HSR Item ***9.57.2-***Providing and fixing on wall face Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 2. 110 mm diameter **HSR Rate(Rs.) 200.00 Through Rate**	Metre	10.973	200.00	2195	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		RWP	*2.00*	*5.486*	*0.000*	*0.000*	*10.973*
							10.973
10	HSR	HSR Item ***9.58.5.2-***Providing and fixing on wall face Unplasticised - PVC moulded fittings/ accessories for Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 5.2. Bend 87.5° 110 mm bend **HSR Rate(Rs.) 93.00 Through Rate**	Each	4.000	93.00	372	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		BEND	*1.00/4.000*	*0.000*	*0.000*	*0.000*	*4.000*
							4.000
11	HSR	HSR Item ***6.1.6-***Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 6. 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size) **HSR Rate(Rs.) 2442.00 Through Rate**	cum	4.786	2442.00	11687	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		column	*8.00*	*1.981*	*1.981*	*0.152*	*4.786*
							4.786
12	HSR	HSR Item ***6.30.1-***Centering and shuttering including strutting, propping etc. and removal of form for 1. Foundations, footings, bases of columns, etc. for mass concrete **HSR Rate(Rs.) 156.00 Through Rate**	Sqm	11.900	156.00	1856	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		footing	*16.00*	*1.829*	*0.305*	*0.000*	*8.926*
		footing	*8.00*	*0.457*	*0.305*	*0.000*	*1.115*
		footing	*8.00*	*0.762*	*0.305*	*0.000*	*1.859*
							11.900
13	HSR	HSR Item ***7.21.2-***Brick work with common burnt clay non-modular bricks of class designation 10.5 in foundation and plinth in: 2. Cement mortar 1:6 (1 cement : 6 coarse sand) **HSR Rate(Rs.) 3531.00 Through Rate**	cum	4.664	3531.00	16469	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		Short	*6.00*	*3.175*	*0.343*	*0.305*	*1.991*
		long	*2.00*	*9.601*	*0.343*	*0.305*	*2.007*
		SHORT	*6.00*	*3.175*	*0.229*	*0.076*	*0.332*

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
		LONG	*2.00*	*9.601*	*0.229*	*0.076*	*0.334*
							4.664
14	HSR	HSR Item ***6.14.1***-Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1. 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size) **HSR Rate(Rs.) 4374.00 Through Rate**	cum	8.805	4374.00	38513	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		Plinth beam	*2.00*	*10.744*	*0.229*	*0.305*	*1.497*
		Plinth beam	*2.00*	*10.058*	*0.229*	*0.305*	*1.402*
		footing	*4.00*	*1.829*	*1.829*	*0.305*	*4.081*
		footing	*4.00*	*0.914*	*0.838*	*0.457*	*1.400*
		footing	*4.00*	*0.457*	*0.762*	*0.305*	*0.425*
							8.805
15	HSR	HSR Item ***6.30.5***-Centering and shuttering including strutting, propping etc. and removal of form for 5. Lintels, beams, plinth beams, girders, bressumers and cantilevers **HSR Rate(Rs.) 296.00 Through Rate**	Sqm	75.460	296.00	22336	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		COLUMN	*16.00*	*0.305*	*3.962*	*0.000*	*19.324*
		COLUMN	*16.00*	*0.610*	*3.962*	*0.000*	*38.648*
		LINTEL BEAM	*12.00*	*3.175*	*0.229*	*0.000*	*8.709*
		LINTEL BEAM	*4.00*	*9.601*	*0.229*	*0.000*	*8.779*
							75.460
16	HSR	HSR Item ***4.14.1***-Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 1. All kinds of soil. **HSR Rate(Rs.) 83.00 Through Rate**	cum	38.284	83.00	3178	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		column	*8.00*	*1.981*	*1.981*	*1.219*	*38.284*
							38.284

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
17	HSR	HSR Item ***6.15.1-***Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor four level, excluding cost of centering, shuttering, finishing and reinforcement : 1. 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size) **HSR Rate(Rs.) 5969.00 Through Rate**	cum	2.949	5969.00	17603	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		COLUMN	*4.00*	*0.305*	*0.610*	*3.962*	*2.949*
							2.949
18	HSR	HSR Item ***6.8.2-***Providing and laying damp-proof course with cement concrete 1:2:4 (1 cement : 2 coarse sand (zone-III): 4 graded stone aggregate 12.5mm nominal size) 2. 40mm thick **HSR Rate(Rs.) 133.00 Through Rate**	Sqm	8.257	133.00	1098	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		dpC	*6.00*	*3.175*	*0.229*	*0.000*	*4.355*
		dpC	*2.00*	*9.601*	*0.229*	*0.000*	*4.390*
		DOOR	*2.00*	*1.067*	*0.229*	*0.000*	*-0.488*
							8.257
19	HSR	HSR Item ***13.22.1-***Supply and fixing Windows frames (Chowkhats) including mullions consisting frame fabricated from sheet roll formed out of 0.58mm thick galvanized sheet (Base steel as per IS 513) with zinc of 120 gm/sqm steel sheet pre coated (as per approved colour) with Polyester paint of 12-16 microns thickness under coat of EPOXY primer and back coat with ALKYD backer of 5-7 microns, total sheet thickness with coating 0.58mm of approved shade, weld less corner assembly with brackets and screws, fixed in position by means of PVC and metal hold fastener with PVC cap complete in all respects as per drawing, design, specification and entire satisfaction of Engineer-in-charge. 1. Windows Outer frame of size 72mm x 55mm and central mullion 72mm x 50mm with Double rebate **HSR Rate(Rs.) 866.00 Through Rate**	Metre	42.863	866.00	37119	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		W	*6.00*	*1.829*	*0.000*	*0.000*	*10.973*
		W	*6.00*	*1.143*	*0.000*	*0.000*	*6.858*
		W	*4.50*	*1.143*	*0.000*	*0.000*	*5.144*
		W	*9.00*	*0.991*	*0.000*	*0.000*	*8.915*
		V	*6.00*	*0.610*	*0.000*	*0.000*	*3.658*
		V	*6.00*	*1.219*	*0.000*	*0.000*	*7.315*
							42.863

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
20	HSR	HSR Item ***12.50.1-***Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. 1. Fixed to steel windows by welding **HSR Rate(Rs.) 91.00 Through Rate**	Kg.	190.950	91.00	17376	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		GRILLS	*1.00/190.950*	*0.000*	*0.000*	*0.000*	*190.950*
							190.950
21	HSR	HSR Item ***6.16-***Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor four level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size). **HSR Rate(Rs.) 6113.00 Through Rate**	cum	24.697	6113.00	150973	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		LINTEL BEAM	*2.00*	*10.744*	*0.229*	*0.229*	*1.123*
		LINTEL BEAM	*2.00*	*10.058*	*0.229*	*0.229*	*1.051*
		SLAB	*1.00*	*10.744*	*10.058*	*0.152*	*16.470*
		SUN SHADE	*1.00*	*2.438*	*0.457*	*0.127*	*0.141*
		BEAM	*2.00*	*10.058*	*0.305*	*0.610*	*3.738*
		BEAM	*2.00*	*10.058*	*0.229*	*0.229*	*1.051*
		BEAM	*2.00*	*10.744*	*0.229*	*0.229*	*1.123*
							24.697
22	HSR	HSR Item ***13.21.2-***Supply and fixing Windows frames (Chowkhats) including mullions consisting frame fabricated from sheet roll formed out of 1.2mm thick galvanized sheet as per IS:277 (Base steel as per IS 513) with zinc of 120 gm/sqm and Powder coated with pure Polyester powder up to 50 microns (as per approved colour), 3 Nos. 100mm butt - hinges 2mm thick, 6 Nos. 1.2mm thick CRCA electroplated stiffner, 6 Nos. M.S hold fast with split and tail welded to stiffner plate 200mm long, receiver for aldrop, weld less corner assembly with brackets and screws, M.S tie rod 50mm x 25mm to be fixed at bottom finished with powder coated total thickness of coating 0.6mm of approved shade, fixed in position including the cost of cement concrete for 1:2:4 for fixing lugs complete in all respects as per drawing, design, specification and entire satisfaction of Engineer-in-charge. 2. Door Frame of size 125mm x 60mm with 37mm wide double rebate for 35mm door shutter **HSR Rate(Rs.) 1240.00 Through Rate**	Metre	15.811	1240.00	19606	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		D	*4.00*	*2.591*	*0.000*	*0.000*	*10.363*
		D	*2.00*	*0.991*	*0.000*	*0.000*	*1.981*
		D	*3.50*	*0.991*	*0.000*	*0.000*	*3.467*
							15.811

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
23	HSR	HSR Item ***10.1.1.1-***Providing and laying of base course of floors consisting of 100 mm thick cement 1:8:16 and 100 mm sand or stone filling. 1.1. Re-compacting excavated soil in plinth under floors, including watering, ramming, consolidating and dressing complete. **HSR Rate(Rs.) 73.00 Through Rate**	cum	2.290	73.00	167	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		UNDER FLOOR	*1.00*	*1.000*	*1.000*	*2.290*	*2.290*
							2.290
24	HSR	HSR Item ***6.30.3-***Centering and shuttering including strutting, propping etc. and removal of form for 3. Suspended floors, roofs, landings, balconies and access platform **HSR Rate(Rs.) 208.00 Through Rate**	Sqm	141.340	208.00	29399	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		SLAB BEAM	*1.00*	*10.287*	*9.601*	*0.000*	*98.768*
		SLAB BEAM	*4.00*	*10.058*	*0.610*	*0.000*	*24.526*
		SLAB BEAM	*4.00*	*9.601*	*0.229*	*0.000*	*8.779*
		SLAB BEAM	*4.00*	*10.135*	*0.229*	*0.000*	*9.267*
							141.340
25	HSR	HSR Item ***5.7.4-***Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 4. In cement mortar **HSR Rate(Rs.) 585.00 Through Rate**	cum	12.998	585.00	7604	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		wall	*2.00*	*1.219*	*0.229*	*3.658*	*2.039*
		wall	*2.00*	*2.134*	*0.343*	*0.762*	*1.115*
		wall	*1.00*	*0.914*	*0.343*	*3.658*	*1.147*
		wall	*1.00*	*9.601*	*0.229*	*3.962*	*8.697*
							12.998
26	HSR	HSR Item ***6.30.7-***Centering and shuttering including strutting, propping etc. and removal of form for 7. Stairs, (excluding landings) except spiral-staircases **HSR Rate(Rs.) 290.00 Through Rate**	Sqm	6.689	290.00	1940	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		stair	*1.00*	*5.486*	*1.219*	*0.000*	*6.689*
							6.689
27	HSR	HSR Item ***7.22.2-***Brick work with common burnt clay non-modular bricks of class designation 7.5 in superstructure above plinth level up to floor IV level in all shapes and sizes in : 2. Cement mortar 1:6 (1 cement : 6 coarse sand) **HSR Rate(Rs.) 4488.00 Through Rate**	cum	29.650	4488.00	133069	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		wall	*6.00*	*3.175*	*0.229*	*2.591*	*11.282*
		wall	*2.00*	*9.601*	*0.229*	*2.591*	*11.373*

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
		d	*2.00*	*1.067*	*0.229*	*2.591*	*-1.264*
		w	*3.00*	*1.219*	*0.229*	*1.829*	*-1.529*
		v	*3.00*	*1.219*	*0.229*	*0.457*	*-0.382*
		above lintel beam	*6.00*	*3.175*	*0.229*	*0.914*	*3.982*
		above lintel beam	*2.00*	*9.601*	*0.229*	*0.914*	*4.014*
		Parapet wall	*2.00*	*10.058*	*0.229*	*0.229*	*1.051*
		Parapet wall	*2.00*	*10.744*	*0.229*	*0.229*	*1.123*
							29.650
28	HSR	HSR Item ***11.9.1-***15 mm cement plaster on rough side of single or half brick wall of mix: 1. 1:4 (1 cement: 4 coarse sand) **HSR Rate(Rs.) 139.00 Through Rate**	Sqm	179.257	139.00	24917	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		wall	*2.00*	*9.601*	*3.962*	*0.000*	*76.088*
		wall	*2.00*	*10.287*	*3.962*	*0.000*	*81.522*
		parapet	*2.00*	*10.287*	*0.914*	*0.000*	*18.813*
		parapet	*2.00*	*9.601*	*0.914*	*0.000*	*17.559*
		d	*2.00*	*1.067*	*2.591*	*0.000*	*-5.528*
		w	*3.00*	*1.219*	*1.829*	*0.000*	*-6.689*
		v	*3.00*	*1.829*	*0.457*	*0.000*	*-2.508*
							179.257
29	HSR	HSR Item ***6.33.6-***Steel reinforcement for R.C.C. work, where not included in the complete rate of RCC, including straightening, cutting, bending, placing in position, binding, wastage, overlaps, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire etc. complete in all respect below plinth level 6. Steel reinforcement for R.C.C. work, where not included in the complete rate of RCC, including straightening, cutting, bending, placing in position, binding, wastage, overlaps, weldedjoints, spacer bars, chairs, stays, hangers and annealed steel wire etc. complete in all respect for all heights/depths/storeys/basements etc. Note- Reinforcement shall be measured in length including hooks, if any, separately for different diameters as actually used in work, excluding overlaps. Wastage, overlaps, couplings, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire or other methods of binding and placing shall not be measured and cost of these items shall be deemed to be included in the rates for reinforcement. **HSR Rate(Rs.) 66.00 Through Rate**	Kg.	3655.670	66.00	241274	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		Lintel	*1.00/234.030*	*0.000*	*0.000*	*0.000*	*234.030*
		Column	*1.00/847.000*	*0.000*	*0.000*	*0.000*	*847.000*
		Plinth beam	*1.00/323.640*	*0.000*	*0.000*	*0.000*	*323.640*

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
		Slab	*1.00 /2251.000*	*0.000*	*0.000*	*0.000*	*2251.000*
							3655.670
		Sub-Component Total Amount				**861631**	
	Main-Component : Const of Delhyan wali choupal						
	Sub-Component :- Electrical Work						
30	HSR	HSR Item ***23.2.1.1***-COPPER WIRING WITH MODULAR SWITCHES IN MS CONDUITS (SURFACE/RECESS) 1.1. Wiring for Light/Fan/call bell point with modular type switch/socket and GI box, Modular type face plate etc in 1.5 sqmm FRLS PVC insulated copper conductor cable in 1.6 mm thick MS conduit pipe. Group A **HSR Rate(Rs.) 645.00 Through Rate**	Each	34.000	645.00	21930	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		Fan Point	*1.00/9.000*	*0.000*	*0.000*	*0.000*	*9.000*
		Light Point	*1.00/25.000*	*0.000*	*0.000*	*0.000*	*25.000*
							34.000
31	HSR	HSR Item ***23.2.4.1***-COPPER WIRING WITH MODULAR SWITCHES IN MS CONDUITS (SURFACE/RECESS) 4.1. Wiring in MS conduit system for 3-pin 5amp. Plug point by using 2 no 1.5 sqmm FRLS copper wire and 1 no 1.5 Sqmm FRLS copper wire , including providing 1 no 5/6 Amp 3/5 pin Modular type socket and 1 no 5/6 Amp Modular type switch required GI Box ,modular face plate etc complete as required Group A **HSR Rate(Rs.) 974.00 Through Rate**	Each	5.000	974.00	4870	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		Group A	*1.00/5.000*	*0.000*	*0.000*	*0.000*	*5.000*
							5.000
32	HSR	HSR Item ***23.2.5.1***-COPPER WIRING WITH MODULAR SWITCHES IN MS CONDUITS (SURFACE/RECESS) 5.1. Wiring in MS conduit system for 3-pin 15amp. Plug point by using 2 no 4 sqmm FRLS copper wire and 1 no 4 Sqmm FRLS copper wire for earthling , including providing 1 no 15/16 Amp 3/6 pin Modular socket and 1 no 15/16 Amp Modular switch required GI Box , modular face plate etc complete as required Group A **HSR Rate(Rs.) 1248.00 Through Rate**	Each	2.000	1248.00	2496	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		Group A	*1.00/2.000*	*0.000*	*0.000*	*0.000*	*2.000*
							2.000

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
33	HSR	HSR Item ***23.8.4-***FITTING AND ACCESSORIES 4. Supply and erection of 10.5 cm dia M.S.Fan box including 8 mm dia 30 cm long M.S. Road made into suitable suspension hook and erected in R.C.C. slab for the erection of fan complete with all labour and material required to complete the job. **HSR Rate(Rs.) 95.00 Through Rate**	Each	8.000	95.00	760	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		Fan box	*1.00/8.000*	*0.000*	*0.000*	*0.000*	*8.000*
							8.000
34	HSR	HSR Item ***23.1.6.1-***COPPER WIRING IN MS CONDUIT (SURFACE/RECESS) 6.1. Wiring main ,sub mains and Circuit wiring in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in MS Conduit etc as required. 1 run of Size 1.50 Sqmm(1/1.40mm) **HSR Rate(Rs.) 138.00 Through Rate**	Metre	50.000	138.00	6900	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		1 run of size 1.5 sq mm (1/1.40 mm)	*1.00*	*50.000*	*0.000*	*0.000*	*50.000*
							50.000
35	HSR	HSR Item ***23.1.6.3-***COPPER WIRING IN MS CONDUIT (SURFACE/RECESS) 6.3. Wiring main ,sub mains and Circuit wiring in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in MS Conduit etc as required. 1 run of Size 4 Sqmm(1/2.24mm) **HSR Rate(Rs.) 194.00 Through Rate**	Metre	20.000	194.00	3880	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		1 run of size 4.0 sq mm (1/2.24 mm	*1.00*	*20.000*	*0.000*	*0.000*	*20.000*
							20.000
36	HSR	HSR Item ***23.22.4.2-***MCCB ,DISTRIBUTION BOARDS, MCB`s, RCCB`s, CHANGE OVER etc. 4.2. Supply and erection of double door sheet steel enclosure distribution board suitable for MCBS and ELCBS etc. recessed in wall including bonding to earth with all labour and material required to complete the job in all respect up to the entire satisfaction of the Engineer-in-Charge of the work. SPN DB Double Door 8 way (2 incoming and 6 outgoing) **HSR Rate(Rs.) 1406.00 Through Rate**	Each	1.000	1406.00	1406	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		8 way SPN Distribution board	*1.00/1.000*	*0.000*	*0.000*	*0.000*	*1.000*
							1.000
37	HSR	HSR Item ***23.22.5.1-***MCCB ,DISTRIBUTION BOARDS, MCB`s, RCCB`s, CHANGE OVER etc. 5.1. Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 6 amp. to 32 amp Single Pole **HSR Rate(Rs.) 145.00 Through Rate**	Each	6.000	145.00	870	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		6-32 amp MCB	*1.00/6.000*	*0.000*	*0.000*	*0.000*	*6.000*
							6.000

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
38	HSR	HSR Item ***23.22.5.3-***MCCB ,DISTRIBUTION BOARDS, MCB`s, RCCB`s, CHANGE OVER etc. 5.3. Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 6 amp. to 32 amp Double POLE **HSR Rate(Rs.) 426.00 Through Rate**	Each	1.000	426.00	426	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		6-32 amp MCB double pole	*1.00/1.000*	*0.000*	*0.000*	*0.000*	*1.000*
							1.000
39	HSR	HSR Item ***24.1.1-***EARTHING AND LIGHTENING ARRESTOR 1. Earthing with GL earth pipe 4.5 m long and 40 mm dia with masonry enclosures on the top etc. (but without charcoal or coke and salt) as required. **HSR Rate(Rs.) 2721.00 Through Rate**	Each	1.000	2721.00	2721	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		a	*1.00/1.000*	*0.000*	*0.000*	*0.000*	*1.000*
							1.000
40	HSR	HSR Item ***24.1.2-***EARTHING AND LIGHTENING ARRESTOR 2. Extra for using salt and char coal/coke for pipe earth electrode as required. **HSR Rate(Rs.) 652.00 Through Rate**	Each	1.000	652.00	652	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		b	*1.00/1.000*	*0.000*	*0.000*	*0.000*	*1.000*
							1.000
41	HSR	HSR Item ***24.1.11-***EARTHING AND LIGHTENING ARRESTOR 11. Providing and laying earth connections from earth electrode with 4.00 mm dia G.I. wire in 15 mm dia G.I. pipe from earth electrode as required. **HSR Rate(Rs.) 189.00 Through Rate**	Metre	5.000	189.00	945	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		c	*1.00*	*5.000*	*0.000*	*0.000*	*5.000*
							5.000
42	HSR	HSR Item ***23.8.11.7-***FITTING AND ACCESSORIES 11.7. Providing and fixing modular type accessories of approved make in existing box including fixing and making necessary connections, complete in all respect. step type Fan Regulator 2 modules 300 watt **HSR Rate(Rs.) 257.00 Through Rate**	Each	8.000	257.00	2056	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		a	*1.00/8.000*	*0.000*	*0.000*	*0.000*	*8.000*
							8.000
43	NS	NS Item -S/E of 10sqmm 2 core aluminium flate cable	Per Metre	50.000	24.00	1200	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		NS	*1.00*	*50.000*	*0.000*	*0.000*	*50.000*
							50.000

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

ITEMS							
Sr. No.	**Type**	**Category/Description / Item Size**	**Unit**	**Quantity**	**Unit Rate (Rs.)**	**Total Amount (Rs.)**	
44	NS	NS Item -S/E of 20 watt LED Tube Light Fitting (Philips / Bajaj / Crompton / Wipro / GE / Havells) make including all patty materials required to complete the job in all respect.	Each	10.000	306.00	3060	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		L	*1.00/10.000*	*0.000*	*0.000*	*0.000*	*10.000*
							10.000
45	HSR	HSR Item ***23.23.2.1-***MISCELLANEOUS 2.1. Supply of GI pipe (B-Class) for suspension rod of ceiling fan including threading if required. 15 mm dia **HSR Rate(Rs.) 135.00 Through Rate**	Metre	8.000	135.00	1080	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		FAN PIPE	*1.00*	*8.000*	*0.000*	*0.000*	*8.000*
							8.000
46	HSR	HSR Item ***20.71.1-***Supply, erection, testing of Ceiling fans IS marked (as per IS code 374) with suitable GI pipe complete in all respects complete as per directions of Engineer-in-charge 1. 48" (1200mm) **HSR Rate(Rs.) 2054.00 Through Rate**	Each	8.000	2054.00	16432	
		Description	**No./Qty**	**Length**	**Breadth**	**Depth**	**Total Qty**
		FAN	*1.00/8.000*	*0.000*	*0.000*	*0.000*	*8.000*
							8.000
		Sub-Component Total Amount				**71684**	
		Component Total Amount				**933315**	
		Grand Total				**933315**	

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Detailed Estimate

Development and Panchayat,Haryana

WORK NAME: Construction of Dalhayan wali choupal on panchyat land at village Ishmaila-9b (Bhupender Singh Hooda VAGY 2023-24)

Final Work Cost Abstract				
Sr.No	**Description**	**Items Amount (Rs)**	**Total Charges (Rs.)**	**Total Amount (Rs.)**
	Main-Component : Const of Delhyan wali choupal			
	Sub-Component: Const of choupal Civil Work	8,61,631	2,06,791	10,68,423
	Sub-Component: Electrical Work	71,684	16,224	87,908
	Main Component Total	**₹9,33,315**	**₹2,23,016**	**₹11,56,331**
	Grand Total	**₹9,33,315**	**₹2,23,016**	**₹11,56,331**

Executive Engineer
Development and Panchayat Division
Executive Engineer, Panchayati Raj[Executive Engineer Rohtak]

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Detailed Estimate

Development and Panchayat,Haryana

WORK NAME: Construction of Dalhayan wali choupal on panchyat land at village Ishmaila-9b (Bhupender Singh Hooda VAGY 2023-24)

Detailed Estimate Abstract Cost (in Rs.)					
Sr. No.	**HSR Amount**	**NS Amount**	**Permission from Other Department**	**All Charges**	**Total Amount**
1.	9,29,055.22	4260.00	0.00	223015.85	11,56,331.07
Total :-	**9,29,055**	**4260**	**0**	**223016**	**11,56,331**

Package-Wise Abstract Cost (in Rs.)					
Sr. No.	**Package Description**	**HSR Amount**	**NS Amount**	**Total Amount**	**No. of days require for Completion of this Package by Contractor from dt. of start of work.**
1.	**Package 1-**(Component-1). Const of Delhyan wali choupal	9,29,055.22	4260.00	9,33,315.22	220
	Total :-	**9,29,055**	**4260.00**	**9,33,315**	

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*