Work Name :Const. community Centre at village Assan Kalan block Panipat

Sr. No	Type	Item description	Unit	Total Qty
		Component Name : Const. community Centre at village Assan Kalan block Panipat		
		Sub-Component Name: BOUNDARY WALL WORK		
1	HSR	[10.100.2] [Through Rate] Cement Concrete 1:8:16 Flooring 2. Cement Concrete 1:8:16 with stone aggregate 40 mm size in foundation and plinth.	cum	17.270
2	HSR	[10.30.1] [Through Rate] Providing and laying of chequered precast cement concrete tiles 22 mm thick in footpath and courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). 1. Light shade pigment using white cement	Sqm	5.950
3	HSR	[10.8] [Through Rate] Providing and laying of conglomerate floor 40mm thick cement concrete topping 1:2:4	Sqm	45.140
4	HSR	[10.9] [Through Rate] Providing and laying of Conglomerate floor 25 mm thick cement concrete 1:2:4 on 100 mm cement concrete 1:8:16 and 100 mm sand or stone filling.	Sqm	5.950
5	HSR	[11.5.3] [Through Rate] 12 mm cement plaster of mix : 3. 1:4 (1 cement: 4 fine sand)	Sqm	234.000
6	HSR	[11.59] [Through Rate] Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	465.820
7	HSR	[11.6.1] [Through Rate] 15 mm cement plaster on the rough side of single or half brick wall of mix : 1. 1:4 (1 cement: 4 fine sand)	Sqm	231.840
8	HSR	[11.67.1] [Through Rate] Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : 1. Water thinnable cement primer	Sqm	465.820
9	HSR	[11.74.2] [Through Rate] Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. 2. Two coats	Sqm	465.820
10	HSR	[13.29.2] [Through Rate] Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 2. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg.	600.000
11	HSR	[13.41] [Through Rate] Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories and stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	Kg.	46.000
12	HSR	[4.12.1] [Through Rate] Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in-charge. 1. All kinds of soil	cum	0.340
13	HSR	[4.14.1] [Through Rate] Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 1. All kinds of soil.	cum	68.810

Sr. No	Type	Item description	Unit	Total Qty
14	HSR	[6.15.1] [Through Rate] Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor four level, excluding cost of centering, shuttering, finishing and reinforcement : 1. 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)	cum	13.770
15	HSR	[6.30.5] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 5. Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	120.340
16	HSR	[6.34.6] [Through Rate] Steel reinforcement for R.C.C. work, where not included in the complete rate of RCC, including straightening, cutting, bending, placing in position, binding, wastage, overlaps, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire etc. complete in all respect above plinth level Note:- Reinforcement shall be measured in length including hooks, if any, separately for different diameters as actually used in work , excluding overlaps. Wastage, overlaps, couplings, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire or other methods of binding & placing shall not be measured and cost of these items shall be deemed to be included in the rates for reinforcement. 6. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg.	650.000
17	HSR	[7.21.2] [Through Rate] Brick work with common burnt clay non-modular bricks of class designation 10.5 in foundation and plinth in: 2. Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	1.360
18	HSR	[7.21.4] [Through Rate] Brick work with common burnt clay non-modular bricks of class designation 10.5 in foundation and plinth in: 4. Cement mortar 1:5 (1 cement : 5 coarse sand)	cum	54.920
19	HSR	[7.22.4] [Through Rate] Brick work with common burnt clay non-modular bricks of class designation 10.5 in superstructure above plinth level up to floor IV level in all shapes and sizes in : 4. Cement mortar 1:5 (1 cement : 5 coarse sand)	cum	53.320
		Sub-Component Name: DOOR and WINDOW WORK		
20	HSR	[11.77] [Through Rate] Applying pink primer or aluminium priming coat on wood work including preparation of surface, Knotting and stopping etc.	Sqm	115.960
21	HSR	[11.78] [Through Rate] Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	Sqm	121.270
22	HSR	[12.102.1] [Through Rate] Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 1. 125 mm	Each	26.000
23	HSR	[12.102.2] [Through Rate] Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 2. 100 mm	Each	80.000
24	HSR	[12.103.1] [Through Rate] Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. 1. Single rubber stopper	Each	13.000

Sr. No	Type	Item description	Unit	Total Qty
25	HSR	[12.157.1.1] [Through Rate] Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) : 1.1. For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	Kg.	150.000
26	HSR	[12.158.1] [Through Rate] Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. 1. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side	Sqm	15.000
27	HSR	[12.159.4] [Through Rate] Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): 4. With float glass panes of 8 mm thickness (weight not less than 20 kg/sqm)	Sqm	8.780
28	HSR	[12.160.1] [Through Rate] Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight up to 125 kg, for doors, including cost of cutting floors, embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. 1. With stainless steel cover plate minimum 1.25 mm thickness	Each	3.000
29	HSR	[12.163.2] [Through Rate] Providing and fixing aluminium tubular handle bar 32 mm outer dia, 3.0 mm thick and 2100 mm long with SS screws etc .complete as per direction of Engineer-in-Charge. 2. Powder coated minimum thickness 50 micron aluminium tubular handle bar	Each	6.000
30	HSR	[12.19.1.1.1] [Through Rate] Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : 1.1.1. 35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood	Sqm	20.910
31	HSR	[12.36.1] [Through Rate] Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 1. 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	19.190
32	HSR	[12.7.1.1] [Through Rate] Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately) 1.1. Second class teak wood 35 mm thick shutters	Sqm	20.910

Sr. No	Type	Item description	Unit	Total Qty
33	HSR	[12.9.5.1] [Through Rate] Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick : 5.1. Particle Board 12 mm thick Plain particle board flat pressed, 3 layer or graded wood particle board medium density Grade I, IS : 3087 marked	Sqm	14.630
34	HSR	[12.98.1] [Through Rate] Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 1. 300x16 mm	Each	13.000
35	HSR	[12.99.1] [Through Rate] Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 1. 300x10 mm	Each	13.000
36	HSR	[12.99.3] [Through Rate] Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 3. 200x10 mm	Each	13.000
37	HSR	[12.99.5] [Through Rate] Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 5. 100x10 mm	Each	150.000
38	HSR	[13.29.2] [Through Rate] Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 2. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg.	250.000
39	HSR	[13.3.3.2] [Through Rate] Providing and fixing pressed steel door frames conforming to IS: 4351, manufactured from commercial mild steel sheet of 2.0 mm thickness, including hinges, jamb, lock jamb, bead and if required angle threshold of mild steel angle of section 50x25 mm, or base ties of 2.00 mm, pressed mild steel welded or rigidly fixed together by mechanical means, including M.S. pressed butt hinges 2.5 mm thick with mortar guards, lock strike-plate and shock absorbers as specified and applying a coat of approved steel primer after pre-treatment of the surface as directed by Engineer-in-charge: 3.2. Profile E Fixing with carbon steel galvanised dash fastener of required dia and size (to be paid for separately)	Metre	190.200
40	HSR	[17.5.3] [Through Rate] Compacting Original Ground 3. Compaction of Earthwork Compaction of & preparation of sub grade including loosening, levelling of earth 225 mm thick top layer, rough dressing of soil, final dressing of earth to give level, camber, watering, rolling with road roller, compacting the bed to achieve minimum dry density as given in the Table 3000-2 as per technical clause 305 of MORT&H specifications	Sqm	106.000
		Sub-Component Name: SANITARY WORK		
41	HSR	[22.1.2] [Through Rate] Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: 2. White vitreous chinaware Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap	Each	7.000
42	HSR	[22.101.1.1] [Through Rate] Providing and fixing Unplasticised PVC connection pipe with brass unions : 1.1. 30 cm length 15 mm nominal bore	Each	20.000
43	HSR	[22.104.1] [Through Rate] Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 1. 15 mm nominal bore	Each	15.000

Sr. No	Type	Item description	Unit	Total Qty
44	HSR	[22.105.1] [Through Rate] Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. 1. 15 mm nominal bore	Each	10.000
45	HSR	[22.108.1] [Through Rate] Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 1. 15mm nominal bore	Each	20.000
46	HSR	[22.119.2] [Through Rate] Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. 2. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	Each	4.000
47	HSR	[22.14.2.1] [Through Rate] Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 2.1. Flexible pipe 32 mm dia	Each	7.000
48	HSR	[22.181] [Through Rate] Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Litre	2500.000
49	HSR	[22.210.3] [Through Rate] Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : 3. Oval shape 450x350 mm (outer dimensions)	Each	7.000
50	HSR	[22.22.1] [Through Rate] Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: 1. White vitreous chinaware Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	2.000
51	HSR	[22.222.1.1] [Through Rate] Providing and fixing in position singel socket SWR UPVC soil waste or antisyphonage pipes as per IS 13592 of E.D.C manufacture or of any other reputed firm including cutting, jointing, wastage, but excluding cost of jointing. 1.1. Single Socket Type A 160mm o/d SWR UPVC pipe lines laid complete	Metre	182.880
52	HSR	[22.23.1] [Through Rate] Providing and fixing white vitreous chinaware pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : 1. W.C. pan with ISI marked white solid plastic seat and lid	Each	4.000
53	HSR	[22.25.1] [Through Rate] Providing and fixing white vitreous chinaware flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : 1. One urinal basin with 5 litre white P.V.C. automatic flushing cistern	Each	3.000
54	HSR	[22.38] [Through Rate] Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube up to 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	Each	4.000

Sr. No	Type	Item description	Unit	Total Qty
55	HSR	[22.86.2] [Through Rate] Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot and cold water supply, including all CPVC plain and brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. 2. 20 mm nominal outer dia Pipes	Metre	182.880
		Sub-Component Name: SUB STRUCTURE UPTO PLINTH BEAM		
56	HSR	[4.14.1] [Through Rate] Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 1. All kinds of soil.	cum	209.340
57	HSR	[6.1.6] [Through Rate] Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 6. 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	cum	20.930
58	HSR	[6.14.1] [Through Rate] Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1. 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	cum	35.420
59	HSR	[6.15.1] [Through Rate] Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor four level, excluding cost of centering, shuttering, finishing and reinforcement : 1. 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)	cum	7.830
60	HSR	[6.30.1] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 1. Foundations, footings, bases of columns, etc. for mass concrete	Sqm	76.270
61	HSR	[6.30.5] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 5. Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	68.460
62	HSR	[6.30.6] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 6. Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	63.820
63	HSR	[7.21.4] [Through Rate] Brick work with common burnt clay non-modular bricks of class designation 10.5 in foundation and plinth in: 4. Cement mortar 1:5 (1 cement : 5 coarse sand)	cum	46.940
		Sub-Component Name: SUPER STRUCTURE WORK		
64	HSR	[10.1] [Through Rate] Providing and laying of base course of floors consisting of 100 mm thick cement 1:8:16 and 100 mm sand or stone filling.	Sqm	263.070
65	HSR	[10.100.2] [Through Rate] Cement Concrete 1:8:16 Flooring 2. Cement Concrete 1:8:16 with stone aggregate 40 mm size in foundation and plinth.	cum	2.030
66	HSR	[10.107] [Through Rate] Providing and laying tactile tile (for vision impaired persons as per standards) of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes and patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge. 0 0 0	Sqm	13.390

Sr. No	Type	Item description	Unit	Total Qty
67	HSR	[10.29.1] [Through Rate] Providing and laying of chequered terrazzo tiles 20 to 22 mm thick with graded marble chips of size up to 6 mm in floors, jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing and polishing complete, on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) : 1. Light shade pigment using white cement	Sqm	36.780
68	HSR	[10.37.1] [Through Rate] Providing and fixing of Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 1. 25 mm thick	Sqm	204.280
69	HSR	[10.38] [Through Rate] Providing and fixing of Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	Sqm	18.250
70	HSR	[10.44.1] [Through Rate] Providing and fixing of marble stone flooring with 18 mm thick marble stone, as per sample of marble approved by Engineer-in-charge, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry, including rubbing and polishing complete with : 1. Makrana white second quality	Sqm	37.950
71	HSR	[10.51] [Through Rate] Providing and fixing granite stone in all shades 15mm to 18 mm thick in skirting /dado, risers of steps, pillars and wall facing, laid in any pattern as specified over base of 12mm thick cement coarse sand mortar 1:3 and jointed with white cement slurry mixed with pigment to match the shade of Granite including labour for fixing cramps pins and dowels etc.	Sqm	22.290
72	HSR	[10.57] [Through Rate] Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	Sqm	39.160
73	HSR	[10.58] [Through Rate] Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	197.210
74	HSR	[10.63.2] [Through Rate] Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. 2. Size of Tile 600x600 mm	Sqm	17.700
75	HSR	[10.67.2] [Through Rate] Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours and shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement and matching pigments etc. complete. 2. Size of Tile 600x600 mm	Sqm	4.590
76	HSR	[10.7] [Through Rate] Providing and laying of conglomerate floor 50mm thick cement concrete topping 1:2:4	Sqm	263.070

Work Name :Const. community Centre at village Assan Kalan block Panipat

Sr. No	Type	Item description	Unit	Total Qty
77	HSR	[11.5.3] [Through Rate] 12 mm cement plaster of mix : 3. 1:4 (1 cement: 4 fine sand)	Sqm	500.980
78	HSR	[11.57] [Through Rate] Providing and laying average 6mm thick POP Coating on walls, Ceiling, beams and lintels etc. complete in all respects as approved by the Engineer-In-Charge.	Sqm	344.420
79	HSR	[11.59] [Through Rate] Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	1070.570
80	HSR	[11.6.1] [Through Rate] 15 mm cement plaster on the rough side of single or half brick wall of mix : 1. 1:4 (1 cement: 4 fine sand)	Sqm	569.580
81	HSR	[11.67.1] [Through Rate] Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : 1. Water thinnable cement primer	Sqm	1414.980
82	HSR	[11.74.2] [Through Rate] Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. 2. Two coats	Sqm	1415.000
83	HSR	[22.222.1.2] [Through Rate] Providing and fixing in position singel socket SWR UPVC soil waste or antisyphonage pipes as per IS 13592 of E.D.C manufacture or of any other reputed firm including cutting, jointing, wastage, but excluding cost of jointing. 1.2. Single Socket Type A 110mm o/d SWR UPVC pipe lines laid complete	Metre	36.580
84	HSR	[3.1.2] [Beyond 5km up to 10km per KM] By Mechanical Transport including loading, unloading and stacking 2. Earth	cum	1202.240
85	HSR	[3.1.2] [5km] By Mechanical Transport including loading, unloading and stacking 2. Earth	cum	240.450
86	HSR	[36.31] [THROUGH RATE] Providing, fixing, testing and commissioning of ISI marked (ISI MARK 15683) trolly type CO2 fire extinguisher of capacity 9 kg including valve,horn,suitable handle, discharge hose of one meter long complete in all respect with explosive certificate.	Each	2.000
87	HSR	[36.35] [THROUGH RATE] Providing, fixing, testing and commissioning of ISI marked (ISI MARK 15683) portable ABC multipurpose filled by 90% (MAP) mono amonioum phosphate powders, nitrogen pressurised type fire extinguisher with meter, hose reel rubber pipe with 0.50 mtr long with capacity of 6 kg complete in all respect.	Each	2.000
88	HSR	[4.14.1] [Through Rate] Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 1. All kinds of soil.	cum	8.140
89	HSR	[4.33] [Through Rate] Excavating, supplying and filling of local earth (including royalty) by mechanical transport up to a lead of 1 km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	cum	240.450
90	HSR	[6.15.1] [Through Rate] Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor four level, excluding cost of centering, shuttering, finishing and reinforcement : 1. 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)	cum	13.010

Sr. No	Type	Item description	Unit	Total Qty
91	HSR	[6.16] [Through Rate] Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor four level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).	cum	72.150
92	HSR	[6.30.16.1] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 16.1. Edges of slabs and breaks in floors and walls Under 20 cm wide	Metre	156.240
93	HSR	[6.30.3] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 3. Suspended floors, roofs, landings, balconies and access platform	Sqm	356.920
94	HSR	[6.30.5] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 5. Lintels, beams, plinth beams, girders, bressumers and cantilevers	Sqm	147.470
95	HSR	[6.30.6] [Through Rate] Centering and shuttering including strutting, propping etc. and removal of form for 6. Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	145.280
96	HSR	[6.32.1] [Through Rate] Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc., including cost of de-shuttering and decentring at all levels, over a height of 3.5 m, for every additional height of 1 metre or part thereof (Plan area to be measured). 1. Suspended floors, roofs, landing, beams and balconies (Plan area to be measured)	Sqm	545.790
97	HSR	[6.34.6] [Through Rate] Steel reinforcement for R.C.C. work, where not included in the complete rate of RCC, including straightening, cutting, bending, placing in position, binding, wastage, overlaps, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire etc. complete in all respect above plinth level Note:- Reinforcement shall be measured in length including hooks, if any, separately for different diameters as actually used in work , excluding overlaps. Wastage, overlaps, couplings, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire or other methods of binding & placing shall not be measured and cost of these items shall be deemed to be included in the rates for reinforcement. 6. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg.	14900.000
98	HSR	[7.21.4] [Through Rate] Brick work with common burnt clay non-modular bricks of class designation 10.5 in foundation and plinth in: 4. Cement mortar 1:5 (1 cement : 5 coarse sand)	cum	112.220
99	HSR	[7.27.2] [Through Rate] Half brick masonry with common burnt clay non-modular bricks of class designation 10.5 in foundations and plinth in : 2. cement mortar 1:4 (1 cement : 4 coarse sand)	Sqm	28.230
100	HSR	[9.11.1] [Through Rate] 10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobri leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat: 1. With common burnt clay non-modular brick tile of class designation 10	Sqm	356.920
101	HSR	[9.17.1] [Through Rate] Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : 1. In 75x75 mm deep chase	Metre	156.240

Work Name :Const. community Centre at village Assan Kalan block Panipat

Sr. No	Type	Item description	Unit	Total Qty
102	HSR	[9.18] [Through Rate] Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete.	Each	6.000