Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 4.14.1 **-Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.** **1. All kinds of soil.** **HSR Rate (Rs.) :83.00** **Through Rate** ***Applied Note:*** ***1. Lead : All distances shall be measured over the shortest practical route and not necessarily the route actually taken. Route other than shortest practical route may be considered in cases of unavoidable circumstances and approved by Engineer-in-charge along with reasons in writing. Carriage by animal and mechanical transport shall be reckoned in one km. unit. Distances of 0.5 km. or more shall be taken as 1 km. and distance of less than 0.5 km. shall be ignored.*** ***1. Lead : All distances shall be***												

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

	measured over the shortest practical route and not necessarily the route actually taken. Route other than shortest practical route may be considered in cases of unavoidable circumstances and approved by Engineer-in-charge along with reasons in writing. Carriage by animal and mechanical transport shall be reckoned in one km. unit. Distances of 0.5 km. or more shall be taken as 1 km. and distance of less than 0.5 km. shall be ignored. ***1. Lead : All distances shall be measured over the shortest practical route and not necessarily the route actually taken. Route other than shortest practical route may be considered in cases of unavoidable circumstances and approved by Engineer-in-charge along with reasons in writing. Carriage by animal and mechanical transport shall be reckoned in one km. unit. Distances of 0.5 km. or more shall be taken as 1 km. and distance of less than 0.5 km. shall be ignored.***												
1	LONG WALL	cum	2.00	6.477	0.610	0.762	0.000	6.017	--	0.00 01/04/2023	83.00	**--**	499.41

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
2	SHORT WALL	cum	2.00	1.295	0.610	0.762	0.000	1.203	--	0.00 01/04/2023	83.00	--	99.85
3	PILLER	cum	1.00	1.219	1.219	1.067	0.000	1.586	--	0.00 01/04/2023	83.00	--	131.64
4	TOE WALL	cum	2.00	3.048	0.457	0.229	0.000	0.637	--	0.00 01/04/2023	83.00	--	52.87
5	TOE WALL	cum	1.00	5.639	0.457	0.229	0.000	0.589	--	0.00 01/04/2023	83.00	--	48.89
	Item Total							**10.032**					**832.66**
	HSR Item 6.1.6 **-Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level:** **6. 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)** **HSR Rate (Rs.) :2442.00** **Through Rate**												
6	LONG WALL	cum	2.00	6.477	0.610	0.152	0.000	1.203	--	0.00 01/04/2023	2442.00	--	2,937.73
7	SHORT WALL	cum	2.00	1.295	0.610	0.152	0.000	0.241	--	0.00 01/04/2023	2442.00	--	588.52
8	PILLER	cum	1.00	1.219	1.219	0.152	0.000	0.227	--	0.00 01/04/2023	2442.00	--	554.33
9	TOE WALL	cum	2.00	3.048	0.457	0.101	0.000	0.283	--	0.00 01/04/2023	2442.00	--	691.09
10	TOE WALL	cum	1.00	5.639	0.457	0.101	0.000	0.262	--	0.00 01/04/2023	2442.00	--	639.80
	Item Total							**2.216**					**5,411.47**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 7.21.2 **-Brick work with common burnt clay non-modular bricks of class designation 10.5 in foundation and plinth in:** **2. Cement mortar 1:6 (1 cement : 6 coarse sand)** **HSR Rate (Rs.) :3968.00 Through Rate**												
11	LONG WALL	cum	2.00	6.439	0.572	0.152	0.000	1.122	--	0.00 07/06/2024	3968.00	--	4,452.10
12	LONG WALL	cum	2.00	6.325	0.457	0.152	0.000	0.881	--	0.00 07/06/2024	3968.00	--	3,495.81
13	LONG WALL	cum	2.00	6.210	0.343	0.457	0.000	1.947	--	0.00 07/06/2024	3968.00	--	7,725.70
14	LONG WALL	cum	2.00	6.096	0.229	0.152	0.000	0.425	--	0.00 07/06/2024	3968.00	--	1,686.40
15	SHORT WALL	cum	2.00	1.334	0.572	0.152	0.000	0.232	--	0.00 07/06/2024	3968.00	--	920.58
16	SHORT WALL	cum	2.00	1.448	0.457	0.152	0.000	0.202	--	0.00 07/06/2024	3968.00	--	801.54
17	SHORT WALL	cum	2.00	1.562	0.343	0.457	0.000	0.490	--	0.00 07/06/2024	3968.00	--	1,944.32
18	SHORT WALL	cum	2.00	1.676	0.229	0.152	0.000	0.117	--	0.00 07/06/2024	3968.00	--	464.26
19	toe wall	cum	2.00	3.048	0.343	0.152	0.000	0.319	--	0.00 07/06/2024	3968.00	--	1,265.79
20	toe wall	cum	2.00	3.048	0.229	0.229	0.000	0.319	--	0.00 07/06/2024	3968.00	--	1,265.79
21	toe wall	cum	1.00	5.639	0.343	0.152	0.000	0.295	--	0.00 07/06/2024	3968.00	--	1,170.56

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
22	toe wall	cum	1.00	5.639	0.229	0.229	0.000	0.295	--	0.00 07/06/2024	3968.00	--	1,170.56
	Item Total							**6.644**					**26,363.41**
	HSR Item 6.10 **-Providing and applying a coat of residual petroleum bitumen of grade of VG-10 of approved quality using 1.7kg per square metre on damp proof course after cleaning the surface with brushes and finally with apiece of cloth lightly soaked in kerosene oil.** **HSR Rate (Rs.) :90.00** **Through Rate**												
23	wall	Sqm	1.00	6.096	0.229	0.000	0.000	1.394	--	0.00 01/04/2023	90.00	--	125.46
24	wall	Sqm	2.00	1.905	0.229	0.000	0.000	0.871	--	0.00 01/04/2023	90.00	--	78.39
	Item Total							**2.265**					**203.85**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 6.9.1 **-Providing and laying damp-proof course with cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20mm nominal size)** **1. 50 mm thick** **HSR Rate (Rs.) :202.00** **Through Rate**												
25	area same as 6.10	Sqm	1.00	2.260	1.000	0.000	0.000	2.260	--	0.00 01/04/2023	202.00	--	456.52
	Item Total							**2.260**					**456.52**
	HSR Item 7.22.2 **-Brick work with common burnt clay non-modular bricks of class designation 10.5 in superstructure above plinth level up to floor IV level in all shapes and sizes in :** **2. Cement mortar 1:6 (1 cement : 6 coarse sand)** **HSR Rate (Rs.) :4488.00** **Through Rate**												
26	long wall	cum	1.00	6.096	0.229	3.048	0.000	4.248	--	0.00 07/06/2024	4488.00	--	19,065.02
27	short wall	cum	2.00	1.905	0.229	2.134	0.000	1.858	--	0.00 07/06/2024	4488.00	--	8,338.70
28	pillers	cum	2.00	0.229	0.229	3.048	0.000	0.319	--	0.00 07/06/2024	4488.00	--	1,431.67
29	parapet	cum	2.00	6.096	0.229	0.305	0.000	0.850	--	0.00 07/06/2024	4488.00	--	3,814.80

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
30	....	cum	2.00	2.438	0.229	0.305	0.000	0.340	--	0.00 07/06/2024	4488.00	--	1,525.92
	Item Total							**7.615**					**34,176.11**
	HSR Item 7.38 **-Honey-comb brick work 10 / 11.4 cm thick with common burnt clay bricks of class designation 10.5 in super structure above plinth level up to floor IV level with cement mortar 1:4 (1 cement : 4 coarse sand).** **HSR Rate (Rs.) :327.00** **Through Rate**												
31	walls	Sqm	2.00	1.676	0.914	0.000	0.000	3.066	--	0.00 01/04/2023	327.00	--	1,002.58
	Item Total							**3.066**					**1,002.58**
	HSR Item 6.30.1 **-Centering and shuttering including strutting, propping etc. and removal of form for** **1. Foundations, footings, bases of columns, etc. for mass concrete** **HSR Rate (Rs.) :156.00** **Through Rate**												
32	column base	Sqm	4.00	1.219	0.229	0.000	0.000	1.115	--	0.00 01/04/2023	156.00	--	173.94
33	...	Sqm	4.00	0.762	0.305	0.000	0.000	0.929	--	0.00 01/04/2023	156.00	--	144.92

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
34	...	Sqm	1.00	6.096	3.048	0.000	0.000	18.581	--	0.00 01/04/2023	156.00	--	2,898.64
	Item Total							**20.625**					**3,217.50**
	HSR Item 6.30.6 **-Centering and shuttering including strutting, propping etc. and removal of form for** **6. Columns, Pillars, Piers, Abutments, Posts and Struts** **HSR Rate (Rs.) :262.00** **Through Rate**												
35	....	Sqm	4.00	0.229	3.048	0.000	0.000	2.787	--	0.00 01/04/2023	262.00	--	730.19
	Item Total							**2.787**					**730.19**
	HSR Item 6.30.5 **-Centering and shuttering including strutting, propping etc. and removal of form for** **5. Lintels, beams, plinth beams, girders, bressumers and cantilevers** **HSR Rate (Rs.) :296.00** **Through Rate**												
36	...	Sqm	2.00	6.096	0.381	0.000	0.000	4.645	--	0.00 01/04/2023	296.00	--	1,374.92
37	...	Sqm	1.00	5.639	0.229	0.000	0.000	1.289	--	0.00 01/04/2023	296.00	--	381.54
	Item Total							**5.934**					**1,756.46**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 6.30.3 **-Centering and shuttering including strutting, propping etc. and removal of form for** **3. Suspended floors, roofs, landings, balconies and access platform** **HSR Rate (Rs.) :208.00** **Through Rate**												
38	....	Sqm	1.00	5.639	1.676	0.000	0.000	9.453	--	0.00 01/04/2023	208.00	--	1,966.22
39	....	Sqm	1.00	6.096	0.762	0.000	0.000	4.645	--	0.00 01/04/2023	208.00	--	966.16
40	....	Sqm	2.00	6.096	0.152	0.000	0.000	1.858	--	0.00 01/04/2023	208.00	--	386.46
41	....	Sqm	2.00	2.896	0.152	0.000	0.000	0.883	--	0.00 01/04/2023	208.00	--	183.66
	Item Total							**16.839**					**3,502.50**
	HSR Item 6.14.1 **-Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :** **1. 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)** **HSR Rate (Rs.) :4374.00** **Through Rate**												
42	base	cum	1.00	1.219	1.219	0.152	0.000	0.227	--	0.00 01/04/2023	4374.00	--	992.90

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
43	....	cum	1.00	0.762	0.762	0.305	0.000	0.177	--	0.00 01/04/2023	4374.00	--	774.20
44	tapered	cum	4.00	0.914	0.914	0.152	0.000	0.510	--	0.00 01/04/2023	4374.00	--	2,230.74
45	...	cum	1.00	0.305	0.229	0.610	0.000	0.042	--	0.00 01/04/2023	4374.00	--	183.71
	Item Total							**0.956**					**4,181.55**
	HSR Item 6.15.1 **-Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor four level, excluding cost of centering, shuttering, finishing and reinforcement :** **1. 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)** **HSR Rate (Rs.) :5969.00** **Through Rate**												
46	.....	cum	1.00	0.305	0.229	2.743	0.000	0.191	--	0.00 01/04/2023	5969.00	--	1,140.08
	Item Total							**0.191**					**1,140.08**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 6.16 **-Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor four level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).** **HSR Rate (Rs.) :6113.00** **Through Rate**												
47	slab	cum	1.00	6.096	2.896	0.152	0.000	2.690	--	0.00 01/04/2023	6113.00	--	16,443.97
	Item Total							**2.690**					**16,443.97**
	HSR Item 11.6.2 **-15 mm cement plaster on the rough side of single or half brick wall of mix :** **2. 1:6 (1 cement: 6 fine sand)** **HSR Rate (Rs.) :127.00** **Through Rate**												
48	...	Sqm	2.00	2.134	3.658	0.000	0.000	15.608	--	0.00 07/06/2024	127.00	--	1,982.22
49	....	Sqm	2.00	6.096	3.658	0.000	0.000	44.593	--	0.00 07/06/2024	127.00	--	5,663.31

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
50	....	Sqm	2.00	5.639	0.229	0.000	0.000	2.578	--	0.00 07/06/2024	127.00	--	327.41
51	...	Sqm	2.00	2.438	0.229	0.000	0.000	1.115	--	0.00 07/06/2024	127.00	--	141.61
52	...	Sqm	2.00	0.457	3.048	0.000	0.000	2.787	--	0.00 07/06/2024	127.00	--	353.95
	Item Total							**66.681**					**8,468.50**
	HSR Item 11.5.4 **-12 mm cement plaster of mix :** **4. 1:6 (1 cement: 6 fine sand)** **HSR Rate (Rs.) :104.00** **Through Rate**												
53	....	Sqm	2.00	5.639	3.048	0.000	0.000	34.374	--	0.00 07/06/2024	104.00	--	3,574.90
54	...	Sqm	2.00	1.676	3.048	0.000	0.000	10.219	--	0.00 07/06/2024	104.00	--	1,062.78
55	....	Sqm	2.00	0.305	5.639	0.000	0.000	3.437	--	0.00 07/06/2024	104.00	--	357.45
56	...	Sqm	1.00	0.229	5.639	0.000	0.000	1.289	--	0.00 07/06/2024	104.00	--	134.06
57	....	Sqm	4.00	0.305	3.048	0.000	0.000	3.716	--	0.00 07/06/2024	104.00	--	386.46
58	....	Sqm	1.00	5.639	1.676	0.000	0.000	9.453	--	0.00 07/06/2024	104.00	--	983.11
59	....	Sqm	1.00	6.096	0.762	0.000	0.000	4.645	--	0.00 07/06/2024	104.00	--	483.08
	Item Total							**67.133**					**6,981.84**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 11.60 **-Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.** **HSR Rate (Rs.) :59.00** **Through Rate**												
60	....	Sqm	1.00	80.650	1.000	0.000	0.000	80.650	--	0.00 01/04/2023	59.00	--	4,758.35
	Item Total							**80.650**					**4,758.35**
	HSR Item 11.97.1 **-Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :** **1. Two or more coats applied on walls @ 1.25 litre/10 sqm over and including one coat of Special primer applied @ 0.75 litre /10 sqm** **HSR Rate (Rs.) :71.00** **Through Rate**												
61	.....	Sqm	1.00	80.650	1.000	0.000	0.000	80.650	--	0.00 01/04/2023	71.00	--	5,726.15
	Item Total							**80.650**					**5,726.15**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 10.1 **-Providing and laying of base course of floors consisting of 100 mm thick cement 1:8:16 and 100 mm sand or stone filling.** **HSR Rate (Rs.) :260.00** **Through Rate**												
62	....	Sqm	1.00	6.096	3.048	0.000	0.000	18.581	--	0.00 01/04/2023	260.00	--	4,831.06
63	....	Sqm	1.00	5.639	1.676	0.000	0.000	9.453	--	0.00 01/04/2023	260.00	--	2,457.78
	Item Total							**28.034**					**7,288.84**
	HSR Item 10.7 **-Providing and laying of conglomerate floor 50mm thick cement concrete topping 1:2:4** **HSR Rate (Rs.) :216.00** **Through Rate**												
64	....	Sqm	1.00	6.096	3.048	0.000	0.000	18.581	--	0.00 01/04/2023	216.00	--	4,013.50
65	....	Sqm	1.00	5.639	1.676	0.000	0.000	9.453	--	0.00 01/04/2023	216.00	--	2,041.85
	Item Total							**28.034**					**6,055.35**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 10.50.1 **-Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.** **1. Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.** **HSR Rate (Rs.) :2707.00** **Through Rate**												
66	....	Sqm	1.00	5.639	1.676	0.000	0.000	9.453	--	0.00 01/04/2023	2707.00	--	25,589.27
67	....	Sqm	3.00	1.829	0.305	0.000	0.000	1.672	--	0.00 01/04/2023	2707.00	--	4,526.10
	Item Total							**11.125**					**30,115.37**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 9.11.1 **-10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobri leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat:** **1. With common burnt clay non-modular brick tile of class designation 10** **HSR Rate (Rs.) :488.00** **Through Rate**												
68	...	Sqm	1.00	18.500	8.000	0.000	0.000	148.000	--	0.00 01/04/2023	488.00	--	72,224.00
	Item Total							**148.000**					**72,224.00**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 9.14.1 **-Providing and laying brick tiles over mumty roofs, grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement, over 12 mm layer of cement mortar 1:3 (1 cement : 3 fine sand) and finished neat:** **1. With common burnt clay non-modular brick tiles of class designation 10** **HSR Rate (Rs.) :374.00** **Through Rate**												
69	roof	Sqm	1.00	5.639	2.438	0.000	0.000	13.750	--	0.00 01/04/2023	374.00	--	5,142.50
	Item Total							**13.750**					**5,142.50**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*

Template Item Description Details

Name of Template: **BUS Q SHELTOR AT BLOCK LAKHAN MAJRA (NEWW)**

Sr. No.	HSR ITEM/Description	Unit	No.	L	B	D	Qty	Total Qty	Calculated Applicable Rate (Rs)	Premium %age (Date)	HSR Rate with Premium (Rs)	Calculated Applicable Rate With Premium (Rs)	Amount(Rs)
	HSR Item 13.41 **-Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories and stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).** **HSR Rate (Rs.) :396.00** **Through Rate**												
70	railing	Kg.	1.00	0.000	0.000	0.000	120.000	120.000	--	0.00 01/04/2023	396.00	**--**	47,520.00
	Item Total							**120.000**					**47,520.00**
	Grand Total							**728.177**					**2,93,699.75**

Disclaimer - *Sufficient efforts have been made to make the online calculations accurately. But, calculations are required to be cross checked by each user at each level. Dealing officials will be responsible for checking the accuracy of all Calculation in the estimate in all respect.*