**Detailed Notice Inviting Tender**
**(DNIT)**

# GOVERNMENT OF HARYANA

## Municipal Corporation/Urban Local Bodies

**Name of work:** CONSTRUCTION OF WELCOME GATE AT UGRAKHERI T POINT SANOLI ROAD IN WARD NO. 13, MC PANIPAT

**Estimate Cost:** **Rs 46.08 Lakhs**

## KEY DATES

| | | | |
|---|---|---|---|
| **1.** | **Date of Issue of Notice Inviting Bid** | : | Date **28/07/2026** |
| **2.** | **Period of availability of Bidding Documents on website http://etenders.hry.nic.in** | : | **From 28/07/2026 To 04/08/2026** |
| **3.** | **Time, Date of Pre-bid Meeting** | : | Not Applicable |
| **4.** | **Deadline for Receiving Bids online** | : | Date **04/08/2026** at **09:00** hrs |
| **5.** | **Opening of Bids (Tender Document fee &Earnest Money Declaration Form)** | : | Date **04/08/2026** at **09:00** hrs |
| **6.** | **Time and Date for opening of Part-I of the Bid (Technical Qualification Part)** | : | Date **04/08/2026** at **09:00** hrs |
| **7.** | **Time and Date of opening of Part-II of the Bid (Financial Part) of the Bidders who Qualify in Part I of the Bid.** | : | To be intimated. |
| **8.** | **Last Date of Bid Validity** | | Date **02/12/2026** |
| **9.** | **Officer inviting Bids** | : | **Executive Engineer Municipal Corporation Panipat Municipal Corporation/Urban Local Bodies** |

# BILL OF QUANTITIES

## Name of work:-CONSTRUCTION OF WELCOME GATE AT UGRAKHERI T POINT SANOLI ROAD IN WARD NO. 13, MC PANIPAT

### HSR ITEMS:

| Sr. No | Description of Item with brief specification and reference to book of specification. | Quantity | Unit | Rate to be quoted by the contractor/ society | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 1. | [10.100.2]Cement Concrete 1:8:16 Flooring 2. Cement Concrete 1:8:16 with stone aggregate 40 mm size in foundation and plinth. [Through Rate] | 0.97 | cum | | |
| 2. | [10.42]Extra for pre finished nosing in treads of steps of Kota stone/ sand stone slab. [Through Rate] | 136.34 | Metre | | |
| 3. | [11.5.4]12 mm cement plaster of mix : 4. 1:6 (1 cement: 6 fine sand) [Through Rate] | 137.17 | Sqm | | |
| 4. | [11.6.2]15 mm cement plaster on the rough side of single or half brick wall of mix : 2. 1:6 (1 cement: 6 fine sand) [Through Rate] | 137.17 | Sqm | | |
| 5. | [11.68.3]Applying priming coat: 3. With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works [Through Rate] | 11.15 | Sqm | | |
| 6. | [11.84.1]Painting over the wooden/metal surface with aluminium paint of approved brand and manufacture to give an even shade . 1. Two or more coats on new work [Through Rate] | 11.15 | Sqm | | |
| 7. | [13.29.2]Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 2. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works [Through Rate] | 1300.00 | Kg. | | |
| 8. | [17.23.2]Water Bound Macadam Grading - II 2. Water Bound Macadam (53mm to 22.4 mm)Grading II with screenings Type “B” (11.2 mm aggregates) Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/ vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/ binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density complete as per technical clause 404 of MORT&H specifications [Through Rate] | 76.00 | cum | | |
| 9. | [17.69.2]Interlocking Concrete Block Pavement 2. Providing and Laying 80 mm thick ISI marked Interlocking Paver Blocks conforming to IS 15658:2006/IRC SP 63: 2004 of all shapes and colours in design mix cement M 40 over the bed of 30 mm thick fine sand complete in all respect. [Through Rate] | 82.66 | Sqm | | |

| Sr. No | Description of Item with brief specification and reference to book of specification. | Quantity | Unit | Rate to be quoted by the contractor/ society | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 10. | [23.22.1.3]MCCB ,DISTRIBUTION BOARDS, MCB`s, RCCB`s, CHANGE OVER etc. 1.3. Supply and erection of Modular case circuit breaker single pole/4 pole on existing wall/pedestal/Panel including bounding to earth and making necessary connections required to complete the job in all respect up to the entire satisfaction of the Engineer-in-charge of the work. TRIPLE POLE MCCB 16 to 100 Amp, 25 KA [Through Rate] | 2.00 | Each | | |
| 11. | [23.22.2.1]MCCB ,DISTRIBUTION BOARDS, MCB`s, RCCB`s, CHANGE OVER etc. 2.1. MCCB Enclosure made of Sheet Steel suitable for mounting MCCB of following ratings MCCB up to 125 A FP [Through Rate] | 2.00 | Each | | |
| 12. | [23.22.5.3]MCCB ,DISTRIBUTION BOARDS, MCB`s, RCCB`s, CHANGE OVER etc. 5.3. Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections:- 6 amp. to 32 amp Double POLE [Through Rate] | 12.00 | Each | | |
| 13. | [23.27.2]Supply and erection of Godrej Almirah typeM.S. pedestal made of 50 mm x 50 mm x 6 mm angle iron frame with 3.00 mm thick M.S. sheet covering including shutters with suitable hinges and locking arrangement with Godrej type handle including round bars . The top covering should have downward overhang of 75 mm on all sides of pedestal , having two sets of water proof ventilation holes of suitable size on the sides , at top and bottom , each set containing four Nos. holes to discharge the heat produced by the current . The shutters fixed with rubber gasket of superior quality and of suitable size to make it water proof . The pedestal duly painted both inside and outside with two coats of approved paint and primary coat and its legs are embeded upto the entire depth in 1:2:4 cement concrete block , projected 75 mm all around the pedestal and and 200 mm above the ground level including the cost of all labour and material required to complete the job in all respect upto the entire satisfaction of the Engineer-in-charge of the work:- 2. M.S. pedestal of size 750 mm wide , 900 mm high , 300 mm deep and bottom totally open , duly embeded in cement concrete block of size 900 mm x 450 mm x 200 mm above ground level , having a base of size 1050 mm x 600 mm x 250 mm below ground level . 0 0 [Through Rate] | 1.00 | Each | | |
| 14. | [23.3.6.9]COPPER WIRING IN PVC CONDUIT (SURFACE/RECESS) 6.9. Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in PVC Conduit etc as required. 3 run of Size 1.50 Sqmm(1/1.40mm) [Through Rate] | 120.00 | Metre | | |
| 15. | [24.1.1]EARTHING AND LIGHTENING ARRESTOR 1. Earthing with GL earth pipe 4.5 m long and 40 mm dia with masonry enclosures on the top etc. (but without charcoal or coke and salt) as required. [Through Rate] | 4.00 | Each | | |
| 16. | [24.1.14]EARTHING AND LIGHTENING ARRESTOR 14. Supply and erection of 20mm x 3 mm thick GI, tape fixed with suitable G.I. staples of same size. [Through Rate] | 20.00 | Metre | | |
| 17. | [24.1.2]EARTHING AND LIGHTENING ARRESTOR 2. Extra for using salt and char coal/coke for pipe earth electrode as required. [Through Rate] | 4.00 | Each | | |

| Sr. No | Description of Item with brief specification and reference to book of specification. | Quantity | Unit | Rate to be quoted by the contractor/ society | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 18. | [24.13.23]LT CABLES (Aluminium Conductor, Armoured and Unarmoured) PROVIDING& ERECTION/ LAYING OF PVC/ XLPE INSULATED UNDERGROUND ALUMINIUM CONDUCTOR UNDERGROUND CABLE LOOSE IN EXISTING PIPE OR TRENCHES COMPLETE IN ALL RESPECT WITH NECESSARY CONNECTION UPTO THE ENTIRE SATISFACTION OF ENGINEER IN CHARGE OF THE WORK 23. 16 Sq mm 4 core (UnArm.) [Through Rate] | 150.00 | Metre | | |
| 19. | [24.13.31]LT CABLES (Aluminium Conductor, Armoured and Unarmoured) PROVIDING& ERECTION/ LAYING OF PVC/ XLPE INSULATED UNDERGROUND ALUMINIUM CONDUCTOR UNDERGROUND CABLE LOOSE IN EXISTING PIPE OR TRENCHES COMPLETE IN ALL RESPECT WITH NECESSARY CONNECTION UPTO THE ENTIRE SATISFACTION OF ENGINEER IN CHARGE OF THE WORK 31. 25 Sq mm 4 core (UnArm.) [Through Rate] | 50.00 | Metre | | |
| 20. | [24.8.3]RCC FOUNDATIONS FOR OCTAGONAL POLES 3. Providing RCC foundation of M25 grade (1 Cement:1 Stone aggregate: 2 Coarse sand) i/c excavation, steel reinforcement (Fe 500) @80 kg/cum of concrete contents, concrete cover 50mm, anchor bolts etc. over a bed of PCC 1:5:10 of required dimensions for octagonal poles of various heights as per following specifications complete in all respects and as per directions of Engineer-in-charge<br>5m high pole [Through Rate] | 12.00 | per foundation | | |
| 21. | [34.26]Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including Reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. [Through Rate] | 12.00 | Sqm | | |
| 22. | [34.36]Solar RPM/ Stud Providing and installation of solar cat eye produced from an engineered polymer selected for superior impact resistance and weather-ability. The top of the solar stud should be transparent for solar charging and light output in active mode. The base of the body shall be yellow or neutral white as approved by Engineer In-charge. The marker shall incorporate a solar panel (comprising of solar cells) for converting solar energy into electricity, a storage device for storing the energy, LEDs for illumination and a design for providing 360 degree smooth illumination. The Solar stud shall be round in shape for providing illumination in all directions. The solar stud shall also have high reflective polycarbonate/ methyl methecrylate lenses for conspicuity in passive mode and dual shanks for improved road presence. The solar studs are intended for application directly onto pavement surfaces and shall be applied with epoxy resin adhesives designed for use with raised pavement markers and as supplied by the marker manufacturer separately. The solar cat eye shall be of height: 65 ± 2 mm & Maximum Diameter: 136 ± 5 mm. The body of the solar cat eye shall be resistant to dust and water ingress as per IP 65 standards. The marker shall support a load of 13635 Kg tested in accordance with ASTM D4280. [Through Rate] | 24.00 | Nos. | | |
| 23. | [4.12.1]Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as directed by Engineer-in-charge. 1. All kinds of soil [Through Rate] | 57.72 | cum | | |

| Sr. No | Description of Item with brief specification and reference to book of specification. | Quantity | Unit | Rate to be quoted by the contractor/ society | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 24. | [4.33]Excavating, supplying and filling of local earth (including royalty) by mechanical transport up to a lead of 1 km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. [Through Rate] | 28.97 | cum | | |
| 25. | [5.23.2]Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. 2. Nominal concrete 1:2:4 or leaner mix (i/c equivalent design mix) [Through Rate] | 6.53 | cum | | |
| 26. | [5.70]Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. [Through Rate] | 6.53 | cum | | |
| 27. | [6.1.6]Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 6. 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size) [Through Rate] | 14.63 | cum | | |
| 28. | [6.25.1]Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. 1. All works up to plinth level [Through Rate] | 14.10 | cum | | |
| 29. | [6.25.2]Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. 2. All works above plinth level up to floor IV level [Through Rate] | 31.26 | cum | | |
| 30. | [6.26.1]Extra for providing richer mixes up to plinth and at all floor levels. 1. Providing M-30 grade concrete instead of M-25 grade BMC/ RMC. (Note:- Cement content considered in M-30 is @ 340 kg/cum) [Through Rate] | 45.36 | cum | | |
| 31. | [6.30.1]Centering and shuttering including strutting, propping etc. and removal of form for 1. Foundations, footings, bases of columns, etc. for mass concrete [Through Rate] | 50.59 | Sqm | | |
| 32. | [6.30.3]Centering and shuttering including strutting, propping etc. and removal of form for 3. Suspended floors, roofs, landings, balconies and access platform [Through Rate] | 37.35 | Sqm | | |
| 33. | [6.30.5]Centering and shuttering including strutting, propping etc. and removal of form for 5. Lintels, beams, plinth beams, girders, bressumers and cantilevers [Through Rate] | 47.07 | Sqm | | |
| 34. | [6.30.6]Centering and shuttering including strutting, propping etc. and removal of form for 6. Columns, Pillars, Piers, Abutments, Posts and Struts [Through Rate] | 58.70 | Sqm | | |

| Sr. No | Description of Item with brief specification and reference to book of specification. | Quantity | Unit | Rate to be quoted by the contractor/ society | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 35. | [6.32.1]Extra for additional height in centering, shuttering where ever required with adequate bracing, propping etc., including cost of de-shuttering and decentring at all levels, over a height of 3.5 m, for every additional height of 1 metre or part thereof (Plan area to be measured). 1. Suspended floors, roofs, landing, beams and balconies (Plan area to be measured) [Through Rate] | 74.30 | Sqm | | |
| 36. | [6.33.6]Steel reinforcement for R.C.C. work, where not included in the complete rate of RCC, including straightening, cutting, bending, placing in position, binding, wastage, overlaps, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire etc. complete in all respect below plinth level Note: Reinforcement shall be measured in length including hooks, if any, separately for different diameters as actually used in work , excluding overlaps. Wastage, overlaps, couplings, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire or other methods of binding & placing shall not be measured and cost of these items shall be deemed to be included in the rates for reinforcement. 6. Thermo-Mechanically Treated bars of grade Fe-500D or more [Through Rate] | 1687.00 | Kg. | | |
| 37. | [6.34.6]Steel reinforcement for R.C.C. work, where not included in the complete rate of RCC, including straightening, cutting, bending, placing in position, binding, wastage, overlaps, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire etc. complete in all respect above plinth level Note:- Reinforcement shall be measured in length including hooks, if any, separately for different diameters as actually used in work , excluding overlaps. Wastage, overlaps, couplings, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire or other methods of binding & placing shall not be measured and cost of these items shall be deemed to be included in the rates for reinforcement. 6. Thermo-Mechanically Treated bars of grade Fe-500D or more. [Through Rate] | 8937.51 | Kg. | | |
| 38. | [7.21.2]Brick work with common burnt clay non-modular bricks of class designation 10.5 in foundation and plinth in: 2. Cement mortar 1:6 (1 cement : 6 coarse sand) [Through Rate] | 3.87 | cum | | |
| 39. | [7.22.2]Brick work with common burnt clay non-modular bricks of class designation 10.5 in superstructure above plinth level up to floor IV level in all shapes and sizes in : 2. Cement mortar 1:6 (1 cement : 6 coarse sand) [Through Rate] | 3.17 | cum | | |
| 40. | [8.3]Providing and fixing adjustable stainless steel cramps of approved quality, required shape and size, adjustable with stainless steel nuts, bolts and washer (total weight not less than 260 gms), for dry stone cladding fixed on frame work at suitable location, including making necessary recesses in stone slab, drilling required holes etc complete as per direction of the Engineer-in-charge. [Through Rate] | 542.00 | Each | | |
| 41. | [8.9.1.5]Stone work (machine cut edges) for wall lining etc. (veneer work) up to 10 metre height, backing filled with a grout of average 12 mm thick cement mortar 1:3 (1 cement : 3 coarse sand) including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade : (To be secured to the backing and the sides by means of cramps and pins which shall be paid for separately) : 1.5. Red sand stone - exposed face fine dressed with rough backing.30 mm thick [Through Rate] | 164.00 | Sqm | | |

| Sr. No | Description of Item with brief specification and reference to book of specification. | Quantity | Unit | Rate to be quoted by the contractor/ society | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 42. | [9.18]Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete. [Through Rate] | 2.00 | Each | | |
| 43. | [9.57.3]Providing and fixing on wall face Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 3. 150 mm diameter [Through Rate] | 19.00 | Metre | | |
| 44. | [9.58.5.3]Providing and fixing on wall face Unplasticised - PVC moulded fittings/ accessories for Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. 5.3. Bend 87.5°<br><br>150 mm bend [Through Rate] | 6.00 | Each | | |

## NS ITEMS:

| Sr. No | Description of Item with brief specification and reference to book of specification. | Quantity | Unit | Rate(Rs.) to be quoted by the contractor/ society | |
|---|---|---|---|---|---|
| | | | | In figures | In words |
| 1. | Automatic Control Panel fabricated with 16 SWG CRCA sheet outdoor type with 25A Contactor, 63A MCCB, 24 Hr. Timer and Revese/ Forward Switch. | 1.00 | Each | | |
| 2. | Providing and Fixing of Decorative pole of 5mtr high made of galvanised Mild steel pipes fitted with cast aluminium embellishments duly polyurethane paint coated with cast aluminium base cover. Pole Bottom Dia- 139.7x3.6mm (1 mtr), Top Dia -_ 76.1x3.2mm (2.5 mtr) Base Plate Size is 250x250x12mm Foundation Bolt 16x600x4 Nos. with Single Arm Bracket MF-82A height will be 1.5 Mtr. Long with Suitable pipes and Bracket will be completed with Aluminium Castings as per approved design and LED decorative drop down light 50w made of aluminium housing fitted with PMMA diffuser, Light Dimensions is 500x370 (With-Philips/Fulhame/HR Driver and10KVA SPD)complete in all respect as per the direction of the officer-in-charge | 12.00 | Each | | |
| 3. | Providing and fixing of LED Lights LED IP-65 flood light fixture made of die cast Aluminium housing fitted with toughened glass. (With LED's RGB of 50 W including driver complete in all respect as per entire satisfaction of engineer incharge | 10.00 | Each | | |
| 4. | Providing and fixing of Sitting Lion Sculpture made of FRP (Fiber Reinforced Plastic) of overall height 7-6` (2286 mm), proportionately designed with majestic posture and fine artistic detailing. The sculpture shall be manufactured using high-quality FRP with MS internal frame for strength and durability, suitable for outdoor installation complete in all respect as per the direction of engineer charge | 2.00 | Each | | |
| 5. | Providing and fixing of Stainless steel letter of 304 grade 25mm sides without light complete in all respect upto the entire satisfaction of engineer in charge. | 1440.00 | per | | |
| 6. | Providing and fixing of Stone cladding on GATE of 50 to 60mm thick Pink and red Sandstone of Bansi pahadpur with carving, grinding, polishing and finishing as per the architecture drawing with fittings complete in all respect as per the direction of engineer incharge | 107.00 | Sqm | | |
| 7. | Providing and fixing of Profile light of size 35 x 30mm with aluminium casing of 4500 k including cost of driver complete in all respect | 51.00 | Metre | | |

**Total Bid Price (in figures) ----------**

**(in words) ----------**

**Signature_____**